

## EASTERN AREAS LOW PRESSURE SEWER SYSTEM

### COST ESTIMATES

ITEM	UNIT	QUANTITY	UNIT PRICE (\$)	TOTAL (\$)
<b>SEWER PIPES (mm)</b>				2593418
100	M	7236	50	361800
150	M	19308	55	1061940
200	M	7240	130	941200
250	M	1609	142	228478
<b>FORCEMAINS (mm)</b>				604280
150	M	3218	55	176990
200	M	2413	130	313690
250	M	800	142	113600
<b>LIFT STATIONS</b>				1014000
1	Each	1	235,000	235000
2	Each	1	490,000	490000
3	Each	1	289,000	289000
<b>ROAD CROSSINGS</b>	Each	14	10000	140000
<b>VALVES &amp; FITTINGS (20%)</b>				870340
<b>ENGINEERING (10%)</b>				1044408
<b>CONTINGENCY (30%)</b>				1879934
<b>TOTAL</b>				8146379